



	Compound strengthening	CUM	1	64	0.61	0.15	5.856		
	Earth work	CUM	1	64	0.61	0.15	5.856		
5	Compound wall patch work, including replastering, joint filling, horizontal								
	Patch works	No	23						
6	Removing white wash or colour wash by steel brushing and / or scraping, sand papering and preparing wall surface smooth including repairs to scratches including cost of labour, material complete as per specifications.(Pg								
	Compound painting	Sqm	2	64	1.68		215		
7	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two coat applied @ 1.67L/10 m <sup>2</sup> over and including priming coat of exterior primer applied @ 2.20 kg/10 m <sup>2</sup> ) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.(Pg No.46								
	Compound painting	Sqm	2	64	1.68		215		
8	Removing the old paint from steel and / or other metal surface with flame cleaning and making surface even including cost of material, labour, complete as per specifications.(Pg No.2031.No 20.60 of PWD SR 2023-								
	Compound gate painting removal								
	Small gate	Sqm	2	1.2	1.2		2.88		
	Big gate	Sqm	2	2.44	1.52		7.418		
9	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :Two coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.(Pg No.48								
	Compound gate repainting								
	Small gate	Sqm	2	1.2	1.2		2.88		
	Big gate	Sqm	2	2.44	1.52		7.418		
10	<b>ART Work for Compound</b>								
	ART Work for Compound	SQM	1	3.35	-	1.5	5.025		
11	<b>Electrical items</b>								
	Ceiling Fan [Crompton 3	Nos	2	-	-	-	-		
	8 Module surface box	Nos	1	-	-	-	-		

	12Watts of 4number	Nos	4	-	-	-	-		
12	Providing and fixing in aluminium mosquito window,ventilator,shutters and								
	Windows	Nos	5	1	-	1.4	7		
	Ventilators	Nos	2	0.9	-	0.6	1.08		
13	Drinking water facility								
	Kent Water filter for drinking purpose with electrical and plumbing provision	Nos	1	-	-	-	-		
14	Providing and fixing of Tube light board with electrical provision.								
	Light board of size	SQM	1	1.5	-	0.45	0.675		Not provided in SR Quotation as per market price
15	Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC:Bathroom, cold applied PU membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6 kg/m2 to achieve final DFT (Dry Film Thickness) of 1mm including prime coat of epoxy primer @150 g/m2 and protection with 120gsm Geo-textile over the membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification..(Pg No.149 I.No15.1 of PWD SR 2023-								
	Damp Proof for terrace	SQM	1	7.8	5		39		
	Damp Proof for terrace	SQM	1	7.5	5.8		43.5		
								<b>Total</b>	<b>0.00</b>
								<b>GST 18%</b>	<b>0.00</b>
								<b>Grand Total</b>	<b>0.00</b>
								<b>Local Contribution - 5%</b>	<b>0.00</b>
								<b>ITC Contribution</b>	<b>0.00</b>